

BAREJA NAGARALIKA BAREJA		
DIST: AHMEDABAD.		
BID DOCUMENTS FOR ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA BAREJA, DIST.: AHMEDABAD.		
SCHEDULE NO.	NAME OF WORK	AMOUNT IN RS.
SCHEDULE-B1	ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA AREA	48265.33
	Total Amount Rs.	48265.33
	Say Amount Rs.	48266.00
I/We am/are willing to carry out the work @ _____% Above / Below _____Percentage (should be written in figures and words) of the Estimated rates mentioned above amount of my / our Tender works out as under.		
<u>Estimated Amount</u>		<u>Estimated Amount</u>
Put to Tender Rs.		Put to Tender Rs.
Add % Rs.		Deduct %Rs.
Total Rs.		Total Rs.
(In Words		(In Words

1. The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
2. The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
3. GST and Income tax TDS will be deducted at a source while making payments of bills
4. In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.
5. TPI & PMC Charges will be deducted from the Contractor's each RA Bill up to 3% Maximum.
6. Bidder has to quote rates without GST, GST will be applicable extra on tender rate.

Consulting Civil Engineer
DD (OPC) PVT LTD
Ahmedabad

Municipal Engineer
Bareja Nagarpalika
Bareja

Chief Officer
Bareja Nagarpalika
Bareja

BAREJA NAGARALIKA BAREJA					
DIST: AHMEDABAD.					
BID DOCUMENTS FOR ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA BAREJA, DIST.:					
ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA AREA					
SCHEDULE-B1					
ITEM NO	DESCRIPTION	Quantities Estimated but may be more or less	UNIT	RATE	AMOUNT Rs.
1.00	Earthwork for embankment including breaking clods, dressing with all lead and lift (excluding watering and consolidation)(E) From Borrow area within 3.0 Km. lead.	1.00	Cu.M.	161.22	161.22
2.00	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (i) R.C.C. work	1.00	Cu.M	1030.81	1030.81
3.00	Demolition and disposal of unserviceable materials with all lead and lift.(i) Lime concrete.	1.00	Cu.M	609.26	609.26
4.00	Demolition of Brick work and stone masonry including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (i) In LimeMortar.	1.00	Cu.M	365.87	365.87
5.00	Demolition of Brick work and stone masonry including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.(ii) In Cement Mortar.	1.00	Cu.M	550.40	550.40
6.00	Dismantling tiled of stone floors laid in mortar including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.	1.00	Sqm	47.72	47.72
7.00	Finishing wall with weather proof exterior emulsion paint on wall surface (two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials.etc complete	1.00	Sqm	114.53	114.53
8.00	Applying priming coat over new steel and other metal surface after and including preparing the surface by thoroughly cleaning, oil,grease, dirt and other foreign matter and scoured with brushes fine steel wood, scrapers and sand paper with ready mixed priming paint brushing red lead.	1.00	Sqm	35.17	35.17
9.00	Applying two coats of putty & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth.	1.00	Sqm	40.59	40.59
10.00	Scarifying gravelled macadam or bitumen macadam surface 6 cm to 10 cm.depth including stacking useful materials on road side and disposing off remaining stuff.	1.00	Sqm	39.62	39.62
11.00	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.	1.00	Cu.M	102.93	102.93
12.00	Carting of debris, ruff kota stone, earth or any wastage material on site including loading, unloading within nadiad municipal corporation area as directed by engineer - in- charge. (a) 5.00 KM LEAD	1.00	Cu.M	103.26	103.26
13.00	Construction of 150mm thick Granular Sub Base (Grading I) by providing coarse graded Black Trap material, mixing by mechanical means / rotavator, spreading in uniform layers with motor grader as per required slope and gradient on prepared surface and compacting with vibratory roller at OMC to achieve the desired compaction complete as per MORT & H clause 401	1.00	Cu.M	1387.13	1387.13

BAREJA NAGARALIKA BAREJA					
DIST: AHMEDABAD.					
BID DOCUMENTS FOR ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA BAREJA, DIST.:					
ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA AREA					
SCHEDULE-B1					
ITEM NO	DESCRIPTION	Quantities Estimated but may be more or less	UNIT	RATE	AMOUNT Rs.
14.00	Providing & laying spreading and compacting 150mm thick WBM Grade - II of B.T.M.C. metal 25mm to 90mm size (hand broken) including using 20% (13+7%) filler i.e. stone screening 13.2 mm at the rate 0.16 Cumt. & 0.08 stone dust including spreading in uniform thickness hand packing rolling with vibratory roller 8-10 tonnes in stages to proper grade and camber applying and brooming required types of screening/binding materials to fill up the interstices of coarse aggregate watering and compacting to the required density.	1.00	Cu.M	1512.66	1512.66
15.00	Providing and laying, spreading and compacting 100 mm thick graded stone aggregate to Wet Mix Macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with mechanical means in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density.	1.00	Cu.M	1064.07	1064.07
16.00	Providing and laying cement concrete 1:3:6 (1-Cement : 3- coarse sand : 6- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth	1.00	Cu.M	3005.76	3005.76
17.00	Providing and laying cement concrete 1:4:8 (1- Cement: 4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth	1.00	Cu.M	2680.21	2680.21
18.00	Rolling and consolidation of soling including filling in depression which occur during the process, with power roller 8 tonne to 12 tonne.	1.00	Sqm	22.36	22.36
19.00	Providing and casting in situ controlled cement concrete M-150 for average 75 mm thick Wearing coat laid as directed including tamping ,vibrating, finishing, curing and filling in joints with bitumen complete.	1.00	Cu.M	4210.97	4210.97
20.00	Providing and casting in situ controlled cement concrete M-200 for average 75 mm thick wearing coat laid as directed including tamping, vibrating, finishing, curing and filling in joints with bitumen complete	1.00	Cu.M	5124.28	5124.28
21.00	Supplying promoulded bituminous joint filler.(i) 12mm thick	1.00	Cu.M	553.79	553.79
22.00	Supplying promoulded bituminous joint filler.(ii) 20mm thick	1.00	Cu.M	611.13	611.13
23.00	Supplying promoulded bituminous joint filler.(iii) 25mm thick	1.00	Cu.M	802.87	802.87
24.00	Filling in foundation and plinth with murrum or selected soil in layers of 20cm. thickness including watering, ramming and consolidating etc. complete.	1.00	Cu.M	289.06	289.06
25.00	Providing TMT Bar FE 500D reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level	1.00	kg	76.52	76.52
26.00	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC : SP 63-2018 etc. Complete.	1.00	Sqm.	686.90	686.90

BAREJA NAGARALIKA BAREJA					
DIST: AHMEDABAD.					
BID DOCUMENTS FOR ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA BAREJA, DIST.:					
ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA AREA					
SCHEDULE-B1					
ITEM NO	DESCRIPTION	Quantities Estimated but may be more or less	UNIT	RATE	AMOUNT Rs.
27.00	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 80mm thick with grade of concrete M300 pneumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC : SP 63-2018 etc. Complete.	1.00	Sqm.	824.17	824.17
28.00	Providing and fixing pre-cast concrete kerb stone of gray cement based concrete block 30cm length, 30cm height and 15cm thick of M 200 grade concrete as per approved design and including excavation for fixing in proper line and level, filling the joint with C:M 1:3 (1cement:3fine sand) etc complete.	1.00	Nos.	384.96	384.96
29.00	Renovation of manhole by increasing the height at top including cost of excavation, refitting of c . I. manhole frame and cover curing etc. complete incl. all carting and providing of materials which is required for the purpose (except manhole frame and cover) --For all type manhole by providing RCC 1:2:4 Partition walls with required reinforcement 25 cm thick and circular opening with 500mm clear dia and 0.40 mt. av. ht.	1.00	Nos.	3880.100	3880.10
30.00	RCC precast M.H. Frame & Cover Manufacture. supply & Delivery at store or at site of work precast RCC M.200 Frame & cover suitable to drainage M.H. and as per type design & Drawing including cost of reinforcement M.S. Angles or Flot, curing mold work etc.- Heavy Duty - Frame suitable for 50cm opening of MH	1.00	Nos.	1121.000	1121.00
31.00	RCC precast M.H. Frame & Cover Manufacture. supply & Delivery at store or at site of work precast RCC M.200 Frame & cover suitable to drainage M.H. and as per type design & Drawing including cost of reinforcement M.S. Angles or Flot, curing mold work etc.- Heavy Duty - Cover suitable for 50cm opening of MH	1.00	Nos.	1173.000	1173.00
32.00	Fixing all types of frame and cover in C.C. 1 :2:4 including carting etc. complete excluding cost of R. C. C.	1.00	Nos.	320.850	320.85
33.00	Providing & Laying M.S. Side rail of road thickness with necessary nut bolt plates, fixing as per width applying plates vibrator, electric or diesel on channel comp. with V.D. Systems (Trimix) by using the necessary equipments 7 material & Machinery, such as running screed vibrator on pre-laid M.S. channel for leveling vacuum pumps, floating & power trowling etc. compl. also including grout cutting and filling joint with bituminous every 5 mtr. (ind hardner)	1.00	Sqm	85.85	85.85

BAREJA NAGARALIKA BAREJA					
DIST: AHMEDABAD.					
BID DOCUMENTS FOR ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA BAREJA, DIST.:					
ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA AREA					
SCHEDULE-B1					
ITEM NO	DESCRIPTION	Quantities Estimated but may be more or less	UNIT	RATE	AMOUNT Rs.
34.00	Road marking with hot applied thermoplastic paints with reflectorising glass beads on bitumin surface providing and laying a hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250gms per sqm area, thickness of 2.5mm is excluding of surface applied glass beds as per IRC:35-2015. The finished surface to be level, uniform and free from streaks and holes. zebra patta /bump patta lane/center line/ edge line/cut patta. The white color marking should provide liminance coefficient on cement road shall be min 130 cd/m2/lux and Asphalt road shall be min 100 Mmcd/m2/lux during the service life during the day time. The marking should meet the performance criteria for night time reflectivity, wet reflectivity and skid resistance as mentioned in the section-15 of IRC 35-2015. Warranty for the Retro reflectivity should be two years.	1.00	Sqm	367.72	367.72
35.00	Supplying and fixing cat eye made out from Acrilo beutile sterine injection high compressed molding with reflector made of MMC (prismatic type of size 12cm x 6cm x 2.5cm) provided with bituminous adhesive 100g. with each unit for fixing. (High Intensity grade	1.00	Nos.	375.72	375.72
36.00	Providing and laying 75mm thick compacted open graded per mix bituminous grouting with B.T. aggregates as per required gradation and using 60/70 (VG30) grade bitumen for mixing with aggregated @ 1.99% i.e. 19.90 Kg./M.T. of total mix and bitumen for tack coat at 2.50 Kg./10 sq.mt. for B.T. surface & 4.00 Kg./10 Sq.mt. for W.B.M. surface including heating and mixing in drum mix plant transporting, spreading the same with paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants labour charges etc. using contractor's own drum mix plant and requirement tools etc. complete in accordance with the required specification.	1.00	MT	2964.09	2964.09
37.00	Providing and laying 50mm thick bituminous macadam in one layer with B.T. aggregates as a rate of 0.66 cum/M.T. (as per MOST gradation) & 60/70 (VG30) grade bulk asphalt for tack coat at a rate of 2.50 kg./10 Sqmt. & 60/70 (VG30) Grade bulk bitumen for mixing at rate of 34 Kg/M.T. i.e. 3.40 % by weight of total mix using continuous batching drum mix plant & laid by paver finisher including consolidation with vibratory roller including all necessary equipment, tools, plant, fire wood oil, kerosene, labour charges etc. complete using contractors own machineries.	1.00	MT	4010.25	4010.25
38.00	Providing and laying 25mm thick S.D.B.C. using stone chips as per gradation of M.O.R.T. & H specification using bitumen at rate of 50 Kg./ M.T. including heating the asphalt (60/70 Grade) (VG30) and aggregates by continuous batching drum mix plant machineries equipment, tools, plant, fire wood oil, kerosene and all labour charges etc. complete (using contractors own drum mix plant and machineries.	1.00	MT	5291.39	5291.39
39.00	Providing and Laying Asphalt Painting on B.T Surface with bitumen 60/70 graded at rate 5.00 kg/10 Sqmt by mechanical sprayer in Uniform layer and spreading the stone dust on prepared surface at the rate of 0.03 Cum / 10 / Sqmt. And rolling with smooth wheel pneumatic roller.	1.00	Sqm	80.76	80.76
40.00	Providing & applying evenly priming coat with bitumen Emulsion (SS1) on prepared surface of granular base including cleaning of road surface and sparying primer at the rate of 7.50 Kg. / 10 Smt using mechanical means.	1.00	Sqm	53.03	53.03

BAREJA NAGARALIKA BAREJA					
DIST: AHMEDABAD.					
BID DOCUMENTS FOR ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA BAREJA, DIST.:					
ANNUAL RATE CONTRACT FOR R.C.C. / C.C. ROAD AND ASPHALT ROAD FOR BAREJA NAGARPLAIKA AREA					
SCHEDULE-B1					
ITEM NO	DESCRIPTION	Quantities Estimated but may be more or less	UNIT	RATE	AMOUNT Rs.
41.00	Add for restoration of infrastructures like Kharkuwa. Electncal Line, Telephone cables all types. Water lines. gas line. septic tanks etc. Kharkuwa Repairing 0.00 to 1.5 Mt.	1.00	Nos.	2103.35	2103.35
Total Amount:-					48265.33

Certificate

Stamp with signature of contractor

RA-1									
Item NO.17	Construction of 150mm thick Granular Sub Base (Grading I) by providing coarse graded Black Trap material, mixing by mechanical means / rotavator, spreading in uniform layers with motor grader as per required slope and gradient on prepared surface and compacting with vibratory roller at OMC to achieve the desired compaction complete as per MORT & H clause 401								
G.S.B.									
(A)Lead for aggregates 60 km			R&B SOR 2024-25						
(B)Lead for Bulk Asphalt 60 km									
Sr. No.	Particulars	Basic Rate	Carting per unit for lead						Total Cost @ site of work per unit
			Lead up to 5 Km.	Above 55 Km.					
1	2	3	4						6
1. Cost of Materials for G.S.B.									
1	Matel 40 to 63mm Statement 1, Item 4.1	417.53	90.88	91.00	x	7.52	=	684.32	1192.73
2	Kapachi 10 to 20mm Statement 1, Item 4.5	470.25	81.80	91.00	x	6.77	=	616.07	1168.12
3	Course sand Statement 1, Item 2	279.30	81.80	91.00	x	6.77	=	616.07	977.17
	(A) Cost of Materials inclduing conveyance chares.								
Sr. No.	Material	Qty.	Rate	Per	Amount				
1	Matel 40 to 63mm @ 35%	0.4480	1192.73	Cmt.	534.34				
2	Kapachi 10 to 20mm @ 45%	0.5760	1168.12	Cmt.	672.84				
3	Course sand 2.36mm and below @ 20%	0.2560	977.17	Cmt.	250.16				
			(A)	Total	1457.34				
	(B) Cost of Labour and Machinaries								
Sr. No.	Material	Qty.	Rate	Per	Amount				
1	Labour	0.3500	493.00	Each	172.55	LO22-PG NO 39			
2	Grader	0.0200	1309.32	Hour	26.19	HO19-PG NO 43			
3	Vibratory Roller	0.0200	842.37	Hour	16.85	HO20-PG NO 43			
4	Water Tanker	0.0100	2033.88	Day	20.34	M673 PG NO 26 - 12 HR = 169.49* 12 = 2033.88			
			(B)	Total	235.92				
		Total = (A) + (B)		1693.26	Rs/Cmt				

RA-2					
For W.B.M. Grade - II					
Providing & laying spreading and compacting 150mm thick WBM Grade - II of B.T.M.C. metal 25mm to 90mm size (hand broken) including using 20% (13+7%) filler i.e. stone screening 13.2 mm at the rate 0.16 Cumt. & 0.08 stone dust including spreading in uniform thickness hand packing rolling with vibratory roller8-10 tonnes in stages to proper garde and cmaber applying and brooming required types of screening/binding materials to fill up the interstices of coarse aggregate watering and compacting to the required density.					
	(A)	Hand broken Metal (25 to 90mm) Total Lead 96 Km.			91
	(i)	Basic Rate 25 to 90 mm Size (P.No.07/M273)			Rs. 246.53
	(ii)	Lead up to 5 Km.			90.88
	(iii)	Remaining Lead 55 Km.	KM 91	7.52	684.32
					Total : (A) 1021.73
					Total : (A) 1021.73
					Cumt.
	(B)	Stone Screening 13.20mm size Total Lead 96 Km.			
	(i)	Basic Rate (P. No. 5/I.Code.M176)			Rs. 470.25
	(i)	Lead up to 5 Km.			81.80
		Remaining Lead 55 Km.	KM 91	6.77	616.07
					Total : (B) 1168.12
					Total : (B) 1168.12
					Cumt.
	(C)	Filler Materials Stone Dust With Lead 96 Km.			
	(i)	Basic Rate (P. No. 15/I.No.M566)			Rs. 149.63
	(i)	Lead up to 5 Km.			81.80
		Remaining Lead 55 Km.	KM 91	6.77	616.07
					Total : (C) 847.50
					Total : (C) 847.50
					Cumt.
No.	Materials		Quantity	Rate	Unit Amount
1	B.T. Metal 25 to 90 mm size		1.21	1021.73	Cumt. 1236.29
2	Stone Screening 13.20mm		0.16	1168.12	Cumt. 186.90
3	Filler Materilas Stone Dust		0.08	847.50	Cumt. 67.80
4	Spreading Metal (P.No. 165/I.Code.26018A,I.No.26.2)		1.21	247.28	Cumt. 299.21
5	Spreading stone screening binding materials Stone Dust		0.24	146.01	Cumt. 35.04
6	Rolling & Consolidation (P.No.221/I.Code.26118C,I.No.0)		1.00	58.50	Cumt. 58.50
	Total Rs.				1883.74
	Say Rs.				1883.74

RATE ANALYSIS -3

Providing and laying, spreading and compacting 100 mm thick graded stone aggregate to Wet Mix Macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with mechanical means in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density.						
Cost for 225 Cum						
Sr No	Item	Qty.	Unit	Rate	Amount	
(A)	Labour					
	Mate	0.48	Day	505.00	242.40	L022
	Mazdoor Skilled	2.00	Day	766.00	1532.00	L023
	Mazdoor	10.00	Day	505.00	5050.00	L022
				Total	6824.40	
(B)	Machinery					
	Wet mix plant of 75 Tph capacity	6.60	Hour	990.00	6534	
	Front end loader 1 Cum capacity	6.00	Hour	572.00	3432	
	Paver Finisher	6.00	Hour	1251.00	7506	
	Water Tanker	12.00	Hour	169.49	2033.88	M673-Pg No.18
	Tipper	24.00	Hour	220.00	5280	
	Vibratory roller	3.90	Hour	40.68	158.652	H013-Pg No.35
	add 10 % of cost of carriage to cover cost of loading & unloading				528	
				Total	25472.532	

(C) Material

Sr No	Material	Basic Rate	Upto 5km Lead	Effective Lead	10km to 15km	Effective Lead Rate
1	2	3	4	5	6	7
1	45mm to 22.4mm @ 30%	503.03	81.80	91.00	6.77	697.87
2	22.4mm to 2.36mm @ 40%	436.77	81.80	91.00	6.77	697.87
3	2.36mm to 75 micron Stone dust @ 30%	149.63	81.80	91.00	6.77	697.87

Sr No	Material	Qty	Rate (3) + (7)	Unit	Amount
1	2	3	4	5	6
1	M/c B.T. Metal 45mm To 22.4 mm @ 30%	67.50	1200.90	Cum	81060.75
2	M/c B.T. Kapchi 22.4 to 2.36 mm @ 40%	90.00	1134.64	Cum	102117.6
3	Stone Dust below 2.36 mm size @ 30%	67.50	847.50	Cum	57206.25
Total					240390.6

(F)	Total Cost = A + B + C	=	272687.53	Per 225 Cum
	Add 1% Water Charges	=	2726.88	
	Add 10% Contractor Profit	=	27268.75	
	i.e. Cost Rs.	=	1345.26	
	i.e. Say Rs.	=	1345.26	